



DEFENSE LOGISTICS AGENCY
LAND AND MARITIME
P.O. BOX 3990
COLUMBUS, OHIO 43218-3990

DLA LAND AND MARITIME-VAI

18 August 2025

MEMORANDUM FOR MILITARY/INDUSTRY DISTRIBUTION

SUBJECT: Initial Drafts of various MIL-DTL-38999 Slash Sheets
(see table below for details).

These initial drafts for these subject documents are now available for viewing and downloading from the DLA Land and Maritime-VA Web site:

<https://landandmaritimeapps.dla.mil/Programs/MilSpec/DocSearch.aspx>

Initial Draft	Title	Project Number
MIL-DTL-38999/10C	Connectors, Electrical, Circular, Receptacle, Dummy Stowage, Bayonet Coupling, (MIL-DTL-27599, Series II and MIL-DTL-38999, Series II)	5935-2025-086
MIL-DTL-38999/20J	Connectors, Electrical, Circular, Receptacle, Threaded, Wall Mounting Flange, Removable Crimp Contacts, Series III, Metric	5935-2025-087
MIL-DTL-38999/21D	Connectors, Electrical, Circular, Threaded, Receptacle, Box Mounting Flange, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-088
MIL-DTL-38999/22K	Connectors, Electrical, Circular, Receptacle, Threaded, Dummy Stowage, Series III, Metric	5935-2025-089
MIL-DTL-38999/23D	Connectors, Electrical, Circular, Threaded, Receptacle, Jam-Nut Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-092
MIL-DTL-38999/24K	Connectors, Electrical, Circular, Receptacle, Threaded, Jam-Nut Mounting, Removable Crimp Contacts, Series III, Metric	5935-2025-093
MIL-DTL-38999/25D	Connector, Electrical, Circular, Threaded, Receptacle, Solder Mounting, Hermetic, Solder Contacts, Series III, Metric	5935-2025-094
MIL-DTL-38999/26H	Connectors, Electrical, Plug, Circular, Threaded, Straight, Removable Crimp Contacts, Series III, Metric	5935-2025-095
MIL-DTL-38999/27D	Connectors, Electrical, Circular, Threaded, Receptacle, Weld Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-096
MIL-DTL-38999/28J	Connectors, Electrical, Circular, Nut, Hexagon, Connector Mounting, Series III and IV, Metric	5935-2025-097
MIL-DTL-38999/29D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Pins, Series III, Metric	5935-2025-098
MIL-DTL-38999/30D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Sockets, Series III, Metric	5935-2025-099

Major changes to these documents include removing dimensional equivalents.

Concurrence or comments are required at this Center within 30 days. Late comments will be held for the next coordination of the document. Comments from military departments must be identified as either "Essential" or "Suggested". Essential comments must be justified with supporting data. Military review activities should forward comments to their custodians of this office, as applicable, in sufficient time to allow for consolidating the department reply. Lack of response to this draft will be construed as concurrence.

If these documents are of interest to you, please provide your comments or suggested changes. The point of contact for this document is Mr. Bender, phone number 614-692-9185, facsimile transmission, 614-692-6939, e-mail Jacob.Bender@dla.mil or may be mailed via the US Postal Service to DLA LAND AND MARITIME, ATTN: VAI (Attention: Jacob Bender), P.O. Box 3990, Columbus, OH 43218-3990.

Sincerely,

/SIGNED/

ERIC CANDELARIA
Acting Chief,
Interconnection Branch

CC: David Devine, Robert Schoening, Alan Drais, Eddie Shen, Deborah Thompson

Note: This initial draft, dated August 22, 2025, prepared by DLA-CC has not been approved and is subject to modification. DO NOT USE FOR ACQUISITION PURPOSES.
(Project: 5935-2025-092)

METRIC

MIL-DTL-38999/23D
DRAFT
SUPERSEDING
MIL-DTL-38999/23C
w/AMENDMENT 2
11 August 2022

DETAIL SPECIFICATION SHEET

CONNECTORS, ELECTRICAL, CIRCULAR, THREADED, RECEPTACLE, JAM-NUT MOUNTING, HERMETIC, HERMETIC SOLDER CONTACTS, SERIES III, METRIC

This specification is approved for use by all Departments
and Agencies of the Department of Defense.

The requirements for acquiring the connectors described herein
shall consist of this specification sheet and MIL-DTL-38999.





FIGURE 1. Receptacle, classes N and Y.



MIL-DTL-38999/23D
DRAFT DATED 22 AUGUST 2025



Shell size	Shell size code	A dia ± .3	B flat + .10 - .15	C dia + .1 - .2	D + .13 - .03	E dia ± .3	F dia max	G thread
9	A	30.2	16.53	17.4	2.39	15.3	15.9	M17X1-6g 0.100R
11	B	34.9	19.07	20.6	2.39	18.4	18.8	M20X1-6g 0.100R
13	C	38.1	23.82	25.4	2.39	21.6	23.8	M25X1-6g 0.100R
15	D	41.3	26.97	28.5	2.39	24.8	26.8	M28X1-6g 0.100R
17	E	44.5	30.15	See note 6	2.39	28.0	30.8	M32X1-6g 0.100R
19	F	49.2	33.32	See note 6	3.58	31.2	33.8	M35X1-6g 0.100R
21	G	52.4	36.50	See note 6	3.58	34.3	36.8	M38X1-6g 0.100R
23	H	55.6	39.67	41.2	3.58	37.5	39.8	M41X1-6g 0.100R
25	J	58.7	42.85	44.4	3.58	40.7	42.8	M44X1-6g 0.100R

MIL-DTL-38999/23D
DRAFT DATED 22 AUGUST 2025

FIGURE 1. Receptacle, classes N and Y- Continued.

Shell size	Shell size code	H $\pm .13$	J + .0 - .71	K max		L max
				with pin	with socket	
9	A	1.14	1.5	5.3	5.9	9.1
11	B	1.14	1.5	5.3	5.9	9.1
13	C	1.14	1.5	5.1	5.7	9.1
15	D	1.14	1.5	5.1	5.7	9.1
17	E	1.14	---	5.1	5.7	9.1
19	F	1.91	---	5.1	5.7	9.7
21	G	1.91	---	5.1	5.7	9.7
23	H	1.91	1.5	5.1	5.7	9.7
25	J	1.91	1.5	5.1	5.7	9.7

FIGURE 1. Receptacle, classes N and Y- Continued.

MIL-DTL-38999/23D
DRAFT DATED 22 AUGUST 2025

Shell size	Shell size code	M dia +3, -.0	P +.4 -.1	S ± 4	W +.3 -.1	Z max	O-ring part number M25988/3
9	A	16.3	14.1	27.0	2.6	29.2	-019
11	B	19.4	14.1	31.8	2.6	29.2	-022
13	C	22.7	14.3	34.9	2.6	29.3	-024
15	D	25.9	14.3	38.1	2.6	29.3	-026
17	E	29.0	14.3	41.3	2.6	29.3	-028
19	F	32.2	14.3	46.0	3.4	30.1	-128
21	G	35.4	14.3	49.2	3.4	30.1	-130
23	H	38.6	14.3	52.4	3.4	30.1	-132
25	J	41.7	14.3	55.6	3.4	30.1	-134

NOTES:

1. Dimensions are in millimeters.
2. Modified major diameter: 31.95 - 31.80 mm.
3. Panel thickness: 3.2 - 1.58 mm.
4. Polarizing position N is shown.
5. O-rings: O-ring shall be in accordance with MIL-DTL-25988/3.
6. C and J dimensions define feature required for proper fit in type E panel.
7. F diameter defines thread start.
8. This dimension applies to shell sizes 17, 19, and 21 only .
9. The specified red band location is measured from the front edge of the shell to the back edge of the red band.

FIGURE 1. Receptacle, classes N and Y - Continued.

REQUIREMENTS:

Dimensions and configurations: See figure 1. Interface dimensions shall conform to MIL-DTL-38999.

This connector mates with MIL-DTL-38999/26.

O-ring and hex nut shall be provided with jam-nut receptacles.

For insert arrangements: See MIL-STD-1560.

Connector accessories: See SAE-AS85049.

Part or Identifying Number example:

<u>D38999/</u>	<u>23</u>	<u>Y</u>	<u>A</u>	<u>35</u>	<u>P</u>	<u>N</u>
<u>D38999/</u>	DoD number prefix					
<u>23</u>	Specification sheet number					
<u>Y</u>	Class					
<u>A</u>	Shell size code					
<u>35</u>	Insert arrangement					
<u>P</u>	Contact style					
<u>N</u>	Polarizing positions					

Eyelet contact termination: See MIL-DTL-38999.

Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

Referenced documents. In addition to MIL-DTL-38999, this document references the following:

MIL-DTL-38999/28
MIL-DTL-38999/26
MIL-DTL-25988/3
MIL-STD-1560
SAE-AS85049

CONCLUDING MATERIAL

Custodians:

Army – CR
Navy - AS
Air Force - 85
DLA - CC

Preparing activity:

DLA - CC

(Project: 5935-2025-092)

Review activities:

Army - AR, MI
Navy - EC, MC
Air Force – 19

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at <https://assist.dla.mil>.