



DEFENSE LOGISTICS AGENCY
LAND AND MARITIME
P.O. BOX 3990
COLUMBUS, OHIO 43218-3990

DLA LAND AND MARITIME-VAI

18 August 2025

MEMORANDUM FOR MILITARY/INDUSTRY DISTRIBUTION

SUBJECT: Initial Drafts of various MIL-DTL-38999 Slash Sheets
(see table below for details).

These initial drafts for these subject documents are now available for viewing and downloading from the DLA Land and Maritime-VA Web site:

<https://landandmaritimeapps.dla.mil/Programs/MilSpec/DocSearch.aspx>

Initial Draft	Title	Project Number
MIL-DTL-38999/10C	Connectors, Electrical, Circular, Receptacle, Dummy Stowage, Bayonet Coupling, (MIL-DTL-27599, Series II and MIL-DTL-38999, Series II)	5935-2025-086
MIL-DTL-38999/20J	Connectors, Electrical, Circular, Receptacle, Threaded, Wall Mounting Flange, Removable Crimp Contacts, Series III, Metric	5935-2025-087
MIL-DTL-38999/21D	Connectors, Electrical, Circular, Threaded, Receptacle, Box Mounting Flange, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-088
MIL-DTL-38999/22K	Connectors, Electrical, Circular, Receptacle, Threaded, Dummy Stowage, Series III, Metric	5935-2025-089
MIL-DTL-38999/23D	Connectors, Electrical, Circular, Threaded, Receptacle, Jam-Nut Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-092
MIL-DTL-38999/24K	Connectors, Electrical, Circular, Receptacle, Threaded, Jam-Nut Mounting, Removable Crimp Contacts, Series III, Metric	5935-2025-093
MIL-DTL-38999/25D	Connector, Electrical, Circular, Threaded, Receptacle, Solder Mounting, Hermetic, Solder Contacts, Series III, Metric	5935-2025-094
MIL-DTL-38999/26H	Connectors, Electrical, Plug, Circular, Threaded, Straight, Removable Crimp Contacts, Series III, Metric	5935-2025-095
MIL-DTL-38999/27D	Connectors, Electrical, Circular, Threaded, Receptacle, Weld Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-096
MIL-DTL-38999/28J	Connectors, Electrical, Circular, Nut, Hexagon, Connector Mounting, Series III and IV, Metric	5935-2025-097
MIL-DTL-38999/29D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Pins, Series III, Metric	5935-2025-098
MIL-DTL-38999/30D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Sockets, Series III, Metric	5935-2025-099

Major changes to these documents include removing dimensional equivalents.

Concurrence or comments are required at this Center within 30 days. Late comments will be held for the next coordination of the document. Comments from military departments must be identified as either "Essential" or "Suggested". Essential comments must be justified with supporting data. Military review activities should forward comments to their custodians of this office, as applicable, in sufficient time to allow for consolidating the department reply. Lack of response to this draft will be construed as concurrence.

If these documents are of interest to you, please provide your comments or suggested changes. The point of contact for this document is Mr. Bender, phone number 614-692-9185, facsimile transmission, 614-692-6939, e-mail Jacob.Bender@dla.mil or may be mailed via the US Postal Service to DLA LAND AND MARITIME, ATTN: VAI (Attention: Jacob Bender), P.O. Box 3990, Columbus, OH 43218-3990.

Sincerely,

/SIGNED/

ERIC CANDELARIA
Acting Chief,
Interconnection Branch

CC: David Devine, Robert Schoening, Alan Drais, Eddie Shen, Deborah Thompson

Note: This initial draft, dated August 22, 2025, prepared by DLA-CC has not been approved and is subject to modification.
DO NOT USE FOR ACQUISITION PURPOSES.
(Project: 5935-2025-097)

METRIC

MIL-DTL-38999/28J
DRAFT
SUPERSEDING
MIL-DTL-38999/28H
w/AMENDMENT 1
27 February 2018

DETAIL SPECIFICATION SHEET

CONNECTORS, ELECTRICAL, CIRCULAR, NUT, HEXAGON, CONNECTOR MOUNTING, SERIES III AND IV, METRIC

This specification is approved for use by all Departments
and Agencies of the Department of Defense.

The requirements for acquiring the product described herein
shall consist of this specification sheet and MIL-DTL-38999.




FIGURE 1. Nut, hexagon.



MIL-DTL-38999/28J
DRAFT DATED 22 AUGUST 2025

Dash number	Shell size		A thread size	P hex	X' + .29 - .00	X + .45 - .00
	Series III and MIL-DTL- 38999/43 of series IV	Series IV, MIL-DTL- 38999/44 only				
1	9	-----	M17X1 – 6H (see note 3)	24.00 21.82	4.54	3.17
2	11	-----	M20X1– 6H (see note 4)	27.00 24.99	4.54	3.17
3	13	11	M25X1 – 6H	32.00 29.77	4.54	3.17
4	15	13	M28X1– 6H	36.00 32.91	4.54	3.17
5	-----	15	M31X1 – 6H	41.00 39.26	4.54	3.17
6	17	-----	M32X1 – 6H	37.00 36.12	4.54	3.17
7	-----	17	M34X1 – 6H	41.00 39.25	4.54	3.17
8	19	-----	M35X1 – 6H	41.00 39.25	4.54	3.17
9	21	19	M38X1 – 6H	46.00 42.47	4.54	3.17
10	23	21	M41X1 – 6H	50.00 45.61	4.54	3.17
11	25	23	M44X1 – 6H	51.23 49.25	4.54	3.17
12	-----	25	M47X1 – 6H	55.00 53.54	4.54	3.17

NOTES:

1. Dimensions are in millimeters.
2. Remove all burrs and sharp edges.
3. Modified minor diameter: 16.04 – 16.15 mm (.631 - .636 inches).
4. Modified minor diameter: 19.07 – 19.15 mm (.751 - .754 inches).
5. Standard safety wire holes are drilled. The safety wire openings depicted in the alternate design are crimped. The alternate hex nut with a crimped edge is specified by adding a “-C” to the Part or Identifying Number (PIN).
6. Classes J and M only (includes hex nut finish codes J, M and V): Optional 45° chamfer and blunt start permissible at transition area between major thread diameter and start of first thread.

MIL-DTL-38999/28J
DRAFT DATED 22 AUGUST 2025

FIGURE 1. Nut, hexagon – Continued.

REQUIREMENTS:

Dimensions and configurations: See figure 1.

Material: See table I.

Finish: See table I and MIL-DTL-38999.

Applicable jam-nut connectors: See MIL-DTL-38999, series III and IV.

TABLE I. Material and finish. 1/

Hex nut finish code	Material	Finish	Applicable connector class code
C	Aluminum alloy	Anodic (nonconductive)	C
F	Aluminum alloy	Electroless nickel coating (conductive)	F, G, R
W	Aluminum alloy	Olive-drab cadmium plate over a suitable underplate (conductive)	W
T	Aluminum alloy	Nickel fluorocarbon polymer, non-reflective (conductive)	T
Z	Aluminum alloy	Zinc nickel, non-reflective (conductive)	Z
K	Corrosion resistant steel <u>2/</u>	Passivated (conductive)	K, H, Y
N	Corrosion resistant steel <u>2/</u>	Electrodeposited nickel plating (conductive)	N, S, L
J	Resin with or without filler	Olive-drab cadmium plate over a suitable underplate (conductive)	J
M	Resin with or without filler	Electroless nickel coating, (conductive)	M
V	Resin with or without filler	Unplated (no finish)	J, M

1/ See MIL-DTL-38999.

2/ Shall be cleaned, descaled and passivated in accordance with SAE-AMS2700.

Qualification. Qualification shall be in accordance with MIL-DTL-38999, except only the following tests shall be required:

Examination of product.

Safety wire hole pull-out (see requirement below).

Salt spray (corrosion).

Safety wire pull-out: Safety wire shall not pull out of hex nuts with crimped edges when safety wire NI-CU alloy (MONEL™) (UNS NO4400) or NI-CR alloy (INCONEL™) (UNS NO6600) 0.51 mm (.020 inch)

MIL-DTL-38999/28J
DRAFT DATED 22 AUGUST 2025

diameter in accordance with NASM20995 is threaded through a hole and a pull of 133.5 Newton (30 lb) minimum is applied. Nine pulls total shall be applied. Pulls shall be applied in three directions. Pulling forces shall be applied parallel with the axis of the nut and also perpendicular to the axis of the nut. Three pulls shall be applied parallel to the axis in one direction and three pulls shall be applied parallel to the axis in the opposite direction. An additional three pulls shall be applied perpendicular to axis of nut.

Group A inspection shall consist of examination of product and safety wire pull-out. Sampling for group A inspection shall be as specified in table II.

TABLE II. Group A sampling plan.

Lot size	Sampling size
1 to 13	100 percent
14 to 150	13 units
151 to 280	20 units
281 to 500	29 units
501 to 1,200	34 units
1,201 to 3,200	42 units
3,201 and up	54 units

Part or Identifying Number (PIN) example:

D38999/ 28 -11 F -C

<u>D38999/</u>	MIL number prefix
<u>28</u>	Specification sheet number
<u>-11</u>	Dash number (see figure 1)
<u>F</u>	Finish code (see table I)
<u>C</u>	Safety wire holes

(Standard safety wire holes are drilled. No PIN designator code is used when hex nuts with drilled safety wire holes are specified. When a hex nut with crimped edges is required, a “-C” designator shall be added to the end of the PIN to indicate a crimped design.)

Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes

Referenced documents. In addition to MIL-DTL-38999, this document references the following:

MIL-DTL-38999/43
MIL-DTL-38999/44
NASM20995
SAE-AMS2700

MIL-DTL-38999/28J
DRAFT DATED 22 AUGUST 2025

CONCLUDING MATERIAL

Custodians:

Army – CR
Navy - AS
Air Force - 85
DLA – CC

Preparing activity:

DLA - CC

(Project 5935-2025-097)

Review activities:

Army - AR, MI
Navy - EC, MC, SH
Air Force - 19

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at <https://assist.dla.mil>.