



DEFENSE LOGISTICS AGENCY
LAND AND MARITIME
P.O. BOX 3990
COLUMBUS, OHIO 43218-3990

DLA LAND AND MARITIME-VAI

18 August 2025

MEMORANDUM FOR MILITARY/INDUSTRY DISTRIBUTION

SUBJECT: Initial Drafts of various MIL-DTL-38999 Slash Sheets
(see table below for details).

These initial drafts for these subject documents are now available for viewing and downloading from the DLA Land and Maritime-VA Web site:

<https://landandmaritimeapps.dla.mil/Programs/MilSpec/DocSearch.aspx>

Initial Draft	Title	Project Number
MIL-DTL-38999/10C	Connectors, Electrical, Circular, Receptacle, Dummy Stowage, Bayonet Coupling, (MIL-DTL-27599, Series II and MIL-DTL-38999, Series II)	5935-2025-086
MIL-DTL-38999/20J	Connectors, Electrical, Circular, Receptacle, Threaded, Wall Mounting Flange, Removable Crimp Contacts, Series III, Metric	5935-2025-087
MIL-DTL-38999/21D	Connectors, Electrical, Circular, Threaded, Receptacle, Box Mounting Flange, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-088
MIL-DTL-38999/22K	Connectors, Electrical, Circular, Receptacle, Threaded, Dummy Stowage, Series III, Metric	5935-2025-089
MIL-DTL-38999/23D	Connectors, Electrical, Circular, Threaded, Receptacle, Jam-Nut Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-092
MIL-DTL-38999/24K	Connectors, Electrical, Circular, Receptacle, Threaded, Jam-Nut Mounting, Removable Crimp Contacts, Series III, Metric	5935-2025-093
MIL-DTL-38999/25D	Connector, Electrical, Circular, Threaded, Receptacle, Solder Mounting, Hermetic, Solder Contacts, Series III, Metric	5935-2025-094
MIL-DTL-38999/26H	Connectors, Electrical, Plug, Circular, Threaded, Straight, Removable Crimp Contacts, Series III, Metric	5935-2025-095
MIL-DTL-38999/27D	Connectors, Electrical, Circular, Threaded, Receptacle, Weld Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-096
MIL-DTL-38999/28J	Connectors, Electrical, Circular, Nut, Hexagon, Connector Mounting, Series III and IV, Metric	5935-2025-097
MIL-DTL-38999/29D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Pins, Series III, Metric	5935-2025-098
MIL-DTL-38999/30D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Sockets, Series III, Metric	5935-2025-099

Major changes to these documents include removing dimensional equivalents.

Concurrence or comments are required at this Center within 30 days. Late comments will be held for the next coordination of the document. Comments from military departments must be identified as either "Essential" or "Suggested". Essential comments must be justified with supporting data. Military review activities should forward comments to their custodians of this office, as applicable, in sufficient time to allow for consolidating the department reply. Lack of response to this draft will be construed as concurrence.

If these documents are of interest to you, please provide your comments or suggested changes. The point of contact for this document is Mr. Bender, phone number 614-692-9185, facsimile transmission, 614-692-6939, e-mail Jacob.Bender@dla.mil or may be mailed via the US Postal Service to DLA LAND AND MARITIME, ATTN: VAI (Attention: Jacob Bender), P.O. Box 3990, Columbus, OH 43218-3990.

Sincerely,

/SIGNED/

ERIC CANDELARIA
Acting Chief,
Interconnection Branch

CC: David Devine, Robert Schoening, Alan Drais, Eddie Shen, Deborah Thompson

Note: This initial draft, dated August 22, 2025, prepared by DLA-CC has not been approved and is subject to modification.
DO NOT USE FOR ACQUISITION PURPOSES.
(Project: 5935-2025-089)

METRIC

MIL-DTL-38999/22K
DRAFT
SUPERSEDING
MIL-DTL-38999/22J
w/AMENDMENT 2
11 August 2022

DETAIL SPECIFICATION SHEET

CONNECTORS, ELECTRICAL, CIRCULAR, RECEPTACLE, THREADED, DUMMY STOWAGE, SERIES III, METRIC

This specification is approved for use by all Departments and Agencies of the Department of Defense.

The requirements for acquiring the product described herein shall consist of this specification sheet and MIL-DTL-38999.




FIGURE 1. Dummy stowage receptacle.



MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025

Dimensions					
Shell size	Shell size code	P ± .20	PP ± .20	R1 (see note 4)	R2 (see note 5)
9	A (see note 8)	3.25	5.49	18.26	15.09
9	A1 (see note 6)	3.25	5.49	18.26	15.09
9	A2 (see note 7)	3.25	5.49	18.26	15.09
11	B	3.25	4.93	20.62	18.26
13	C	3.25	4.93	23.01	20.62
15	D	3.25	4.39	24.61	23.01
17	E	3.25	4.93	26.97	24.61
19	F	3.25	4.93	29.36	26.97
21	G	3.25	4.93	31.75	29.36
23	H	3.91	6.15	34.93	31.75
25	J	3.91	6.15	38.10	34.93

FIGURE 1. Dummy stowage receptacle – Continued.


MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025

Dimensions						
Shell size	Shell size code	S ± .3	V + 0.00 - 0.13	V' + 1.4 - 0.0	W ± .3	W'
9	A (see note 8)	23.8	20.83	19.5	2.5	3.65 / 2.2
9	A1 (see note 6)	23.8	20.83	19.5	2.5	3.65 / 2.2
9	A2 (see note 7)	23.8	20.83	19.5	2.5	3.65 / 2.2
11	B	26.2	20.83	19.5	2.5	3.65 / 2.2
13	C	28.6	20.83	19.5	2.5	3.65 / 2.2
15	D	31.0	20.83	19.5	2.5	3.65 / 2.2
17	E	33.3	20.83	19.5	2.5	3.65 / 2.2
19	F	36.5	20.83	19.5	2.5	3.65 / 2.2
21	G	39.7	20.07	18.7	3.2	4.35 / 2.9
23	H	42.9	20.07	18.7	3.2	4.35 / 2.9
25	J	46.0	20.07	18.7	3.2	4.35 / 2.9

NOTES:


1. Dimensions are in millimeters.
2. Flange is solid.
3. Dummy receptacles are used when unmated plugs must be protected.
4. Dimensions required for intermountability with front or rear mounting series I.
5. Dimensions required for intermountability with front mounting series II.
6. Shell size code A1 is for use with size 9 plug mating key polarizations C, E and N, only.
7. Shell size code A2 is for use with size 9 plug mating key polarizations A, B and D, only.
8. Shell size code A (inactive for new design) is for use with legacy systems with size 9 plug mating key polarizations A, B, C, D, E and N.
9. Dimensions V' and W' are for classes J and M, only. Dimensions V and W are for all other classes.

FIGURE 1. Dummy stowage receptacle – Continued.



SHELL SIZE 9, SHELL SIZE CODE A


FIGURE 2. Dummy stowage receptacle, keyway arrangements (shell size 9).



SHELL SIZE 9, SHELL SIZE CODE A1

FIGURE 2. Dummy stowage receptacle, keyway arrangements (shell size 9). – Continued.

MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025




SHELL SIZE 9, SHELL SIZE CODE A2

NOTES:

1. Dimensions are in millimeters.

FIGURE 2. Dummy stowage receptacle, keyway arrangements (shell size 9) - Continued.




SHELL SIZES 11, 13 AND 15

Shell size	Shell size code	A dia	B dia
11	B	15.88/15.60	14.66/14.45
13	C	19.66/19.38	17.50/17.30
15	D	22.84/22.56	20.65/20.44

NOTES:

1. Dimensions are in millimeters.

FIGURE 3. Dummy stowage receptacle, keyway arrangement (shell sizes 11, 13 and 15).



SHELL SIZES 17, 19, 21, 23 AND 25

Shell size	Shell size code	A dia	B dia
17	E	26.01/25.73	23.85/23.64
19	F	28.63/28.40	26.55/26.31
21	G	31.85/31.57	29.70/29.49
23	H	35.03/34.75	32.85/32.66
25	J	38.20/37.92	36.00/35.84

FIGURE 4. Dummy stowage receptacle, keyway arrangement (shell sizes 17, 19, 21, 23 and 25).

MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025

REQUIREMENTS:

Dimensions and configurations: See figures 1 thru 4. Interface dimensions shall conform to MIL-DTL-38999, except as noted.

This dummy stowage receptacle (DSR) mates with qualified plugs in accordance with MIL-DTL-38999/26, MIL-DTL-38999/29, MIL-DTL-38999/30, and MIL-DTL-38999/31.

Air leakage: Testing shall be in accordance with EIA-364-02, except the minimum period of measurement shall be 10 seconds. The air leakage rate shall be no greater than 1 atmospheric cubic inch per hour ($4.55 \times 10^{-3} \text{ cm}^3/\text{s}$). Stowage receptacles shall be mated to connectors having either contacts or inserts removed so that a pressure of 10 lbft/in² (.703 Kg/cm²) can be applied against the insides of the stowage receptacles.

Qualification (**general**): Qualification shall be in accordance with MIL-DTL-38999, conducted on two samples of each shell size, except only the following sequence of tests shall be required:

- Examination of product
- Coupling torque
- Dynamic salt spray (corrosion)
- Air leakage (see requirement)
- Visual and mechanical

Qualification (classes J and M only): Qualification (general) requirements shall apply. The following additional tests shall be required:

- Temperature cycling
- Hydrolytic stability

Group A sampling inspection. Sampling for group A inspection shall be as specified in table I.

TABLE I. Group A sampling plan.

Lot size	Sampling size
1 to 13	100 percent
14 to 150	13 units
151 to 280	20 units
281 to 500	29 units
501 to 1,200	34 units
1,201 to 3,200	42 units
3,201 and up	54 units

MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025

Part or Identifying Number (PIN) example:

<u>D38999/</u>	<u>22</u>	<u>B</u>	<u>W</u>
<u>D38999/</u>	DoD number prefix		
<u>22</u>	Specification sheet number		
<u>B</u>	Shell size code (for shell size codes A, A1 and A2, see note)		
<u>W</u>	Class		

NOTE: Shell size codes A, A1 and A2 for shell size 9 only:

- Shell size code A is a universal configuration for use with plugs with mating key polarizations A, B, C, D, E and N.
- Shell size code A1 is for use with plugs with mating key polarizations C, E or N.
- Shell size code A2 is for use with plugs with mating key polarizations A, B or D.

Class F is not for Navy use. Class F is inactive for use in Air Force new design.

Shell size code A (shell size 9) is inactive for new design. Use shell size codes A1 or A2 for new design.

NOTE: The term PIN is equivalent to the term (part number, identification number, and type designator) which was previously used in this specification.

Application note:

1. Shell size 9, shell size code A (universal configuration), is not recommended for blind mate applications due to the possibility for misalignment between the DSR keyways and the plug keys. Misalignment can potentially damage plug EMI bands.

Change effectivity. Unless otherwise specified by the preparing activity and/or the qualifying activity, all changes from the previous revision of this specification sheet shall become effective within 90 days of the date of publication of the latest revision. If unable to implement changes within the 90 day time period, the manufacturer or value added distributor shall notify the qualifying activity. The qualifying activity shall determine if an extension may be granted.

Disposition of stock. Unless otherwise specified by the qualifying activity and coordinated with the preparing activity, qualified manufacturers and their selling agents or distributors may continue to ship stowage receptacles which were manufactured in accordance with the previous revision of this specification sheet for a period of 18 months from the date of the latest revision, provided that form, fit and function are not affected.

Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

MIL-DTL-38999/22K
DRAFT DATED 22 AUGUST 2025

Referenced documents. In addition to MIL-DTL-38999, this document references the following:

MIL-DTL-38999/26
MIL-DTL-38999/29
MIL-DTL-38999/30
MIL-DTL-38999/31
EIA-364-02

CONCLUDING MATERIAL

Custodians:

Army - CR
Navy - AS
Air Force – 85
DLA - CC

Preparing activity:

DLA - CC

(Project 5935-2025-089)

Review activities:

Army - AR, MI
Navy - EC, MC
Air Force - 19

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at <https://assist.dla.mil>.