



DEFENSE LOGISTICS AGENCY
LAND AND MARITIME
P.O. BOX 3990
COLUMBUS, OHIO 43218-3990

DLA LAND AND MARITIME-VAI

18 August 2025

MEMORANDUM FOR MILITARY/INDUSTRY DISTRIBUTION

SUBJECT: Initial Drafts of various MIL-DTL-38999 Slash Sheets
(see table below for details).

These initial drafts for these subject documents are now available for viewing and downloading from the DLA Land and Maritime-VA Web site:

<https://landandmaritimeapps.dla.mil/Programs/MilSpec/DocSearch.aspx>

Initial Draft	Title	Project Number
MIL-DTL-38999/10C	Connectors, Electrical, Circular, Receptacle, Dummy Stowage, Bayonet Coupling, (MIL-DTL-27599, Series II and MIL-DTL-38999, Series II)	5935-2025-086
MIL-DTL-38999/20J	Connectors, Electrical, Circular, Receptacle, Threaded, Wall Mounting Flange, Removable Crimp Contacts, Series III, Metric	5935-2025-087
MIL-DTL-38999/21D	Connectors, Electrical, Circular, Threaded, Receptacle, Box Mounting Flange, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-088
MIL-DTL-38999/22K	Connectors, Electrical, Circular, Receptacle, Threaded, Dummy Stowage, Series III, Metric	5935-2025-089
MIL-DTL-38999/23D	Connectors, Electrical, Circular, Threaded, Receptacle, Jam-Nut Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-092
MIL-DTL-38999/24K	Connectors, Electrical, Circular, Receptacle, Threaded, Jam-Nut Mounting, Removable Crimp Contacts, Series III, Metric	5935-2025-093
MIL-DTL-38999/25D	Connector, Electrical, Circular, Threaded, Receptacle, Solder Mounting, Hermetic, Solder Contacts, Series III, Metric	5935-2025-094
MIL-DTL-38999/26H	Connectors, Electrical, Plug, Circular, Threaded, Straight, Removable Crimp Contacts, Series III, Metric	5935-2025-095
MIL-DTL-38999/27D	Connectors, Electrical, Circular, Threaded, Receptacle, Weld Mounting, Hermetic, Hermetic Solder Contacts, Series III, Metric	5935-2025-096
MIL-DTL-38999/28J	Connectors, Electrical, Circular, Nut, Hexagon, Connector Mounting, Series III and IV, Metric	5935-2025-097
MIL-DTL-38999/29D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Pins, Series III, Metric	5935-2025-098
MIL-DTL-38999/30D	Connectors, Electrical, Circular, Threaded, Plug, Lanyard Release, Fail-Safe, Removable Crimp Contacts, Sockets, Series III, Metric	5935-2025-099

Major changes to these documents include removing dimensional equivalents.

Concurrence or comments are required at this Center within 30 days. Late comments will be held for the next coordination of the document. Comments from military departments must be identified as either "Essential" or "Suggested". Essential comments must be justified with supporting data. Military review activities should forward comments to their custodians of this office, as applicable, in sufficient time to allow for consolidating the department reply. Lack of response to this draft will be construed as concurrence.

If these documents are of interest to you, please provide your comments or suggested changes. The point of contact for this document is Mr. Bender, phone number 614-692-9185, facsimile transmission, 614-692-6939, e-mail Jacob.Bender@dla.mil or may be mailed via the US Postal Service to DLA LAND AND MARITIME, ATTN: VAI (Attention: Jacob Bender), P.O. Box 3990, Columbus, OH 43218-3990.

Sincerely,

/SIGNED/

ERIC CANDELARIA
Acting Chief,
Interconnection Branch

CC: David Devine, Robert Schoening, Alan Drais, Eddie Shen, Deborah Thompson

Note: This initial draft, dated August 22, 2025, prepared by DLA-CC has not been approved and is subject to modification. DO NOT USE FOR ACQUISITION PURPOSES.
(Project: 5935-2025-095)

METRIC

MIL-DTL-38999/26H
DRAFT
SUPERSEDING
MIL-DTL-38999/26G
w/AMENDMENT 4
11 August 2022

DETAIL SPECIFICATION SHEET

CONNECTORS, ELECTRICAL, PLUG, CIRCULAR, THREADED,
STRAIGHT, REMOVABLE CRIMP CONTACTS, SERIES III, METRIC

This specification is approved for use by all Departments and Agencies of the Department of Defense.

The requirements for acquiring the product described herein shall consist of this specification sheet and MIL-DTL-38999.




FIGURE 1. Plug.



MIL-DTL-38999/26H
DRAFT DATED 22 AUGUST 2025

Shell size	Shell size code	B dia + 0.2 - 0.0	B' dia max (alternate design, classes J and M only)	H max number of ribs (alternate design, classes J and M only)	K max	S dia max	Z max	Z' max (classes J and M only)	External bending moment, minimum, classes J and M (N-m)
9	A	18.4	20.6	12	19.0	21.8	31.0	31.5	8.865
11	B	21.1	23.6	14	21.9	25.0	31.0	31.5	29.492
13	C	25.4	28.2	16	26.1	29.4	31.0	31.5	34.485
15	D	28.7	31.3	18	29.3	32.5	31.0	31.5	40.566
17	E	32.2	34.5	20	32.8	35.7	31.0	31.5	50.781
19	F	34.9	37.3	22	35.5	38.5	31.0	31.5	51.450
21	G	38.1	40.5	24	38.7	41.7	31.0	31.5	80.941
23	H	41.1	43.7	26	41.7	44.9	31.0	31.5	69.810
25	J	44.3	46.8	28	44.9	48.0	31.0	31.5	91.310

NOTES:

1. Dimensions are in millimeters.
2. Knurl design: Straight pattern, or "flute", design optional, provided the design includes the specified flat or scalloped "4 places min" areas between the knurled areas. For the alternate design for classes J and M, the design shall include "H MAX" number of ribs. The minimum length of flats between knurls on the outside diameter of the coupling nut shall be at least 2/3 the length of the coupling nut. For classes T and Z only, knurled areas on the coupling nut may be omitted, provided the minimum number of specified flat or scalloped areas are included.
3. Dimensions B' and Z' are for classes J and M, only. Dimensions B and Z are for all other classes.

FIGURE 1. Plug - Continued.

MIL-DTL-38999/26H
DRAFT DATED 22 AUGUST 2025

REQUIREMENTS:

Dimensions and configuration: See figure 1. Interface dimensions shall be in accordance with MIL-DTL-38999.

This connector mates with MIL-DTL-38999/20, /21, /22, /23, /24, /25 and /27.

For insert arrangements: See MIL-STD-1560.

Connector accessories: SAE-AS85049.

Part or Identifying Number (PIN) example:

<u>D38999/</u>	<u>26</u>	<u>W</u>	<u>A</u>	<u>35</u>	<u>P</u>	<u>N</u>
<u>D38999/</u>	DoD number prefix					
<u>26</u>	Specification sheet number					
<u>W</u>	Class					
<u>A</u>	Shell size code					
<u>35</u>	Insert arrangement					
<u>P</u>	Contact style					
<u>N</u>	Polarizing positions (N is required for normal position)					

Class F is not for Navy use and is inactive for Air Force new design use.

NOTE: The term PIN is equivalent to the term (part number, identification number, and type designator) which was previously used in this specification.

Note: Bending moment torque (class J and M). Details of bending moment torque requirements may be found in MIL-DTL-38999/20. Plug requirements were set at the requirements of the flange mounted receptacles (MIL-DTL-38999/20, representing the strongest mating partner for the plug).

Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

Referenced documents. In addition to MIL-DTL-38999, this document references the following:

MIL-STD-1560
MIL-DTL-38999/20
MIL-DTL-38999/21
MIL-DTL-38999/22
MIL-DTL-38999/23
MIL-DTL-38999/24
MIL-DTL-38999/25
MIL-DTL-38999/27
SAE-AS85049

MIL-DTL-38999/26H
DRAFT DATED 22 AUGUST 2025

CONCLUDING MATERIAL

Custodians:

Army – CR
Navy - AS
Air Force – 85
DLA - CC

Preparing activity:
DLA - CC

(Project 5935-2025-095)

Review activities:

Army - AR, MI
Navy - EC, MC, OS
Air Force - 19

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at <https://assist.dla.mil>.